



## Bid Notice Abstract

### Request for Quotation (RFQ)

**Reference Number** 12107129  
**Procuring Entity** MUNICIPALITY OF ANILAO - ILOILO  
**Title** IMPROVEMENT OF OPCEN (TRANSFORMER FOR OPCEN & APCF) CONVERSION OF SINGLE PHASE LINE TO THREE PHASE LINE  
**Area of Delivery** Iloilo

|                                          |                                                                                                                                                                                     |                              |                     |
|------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|---------------------|
| <b>Solicitation Number:</b>              | 2025-077                                                                                                                                                                            | <b>Status</b>                | <b>Pending</b>      |
| <b>Trade Agreement:</b>                  | Implementing Rules and Regulations                                                                                                                                                  |                              |                     |
| <b>Procurement Mode:</b>                 | Negotiated Procurement - Two Failed Biddings (Sec. 53.1)                                                                                                                            | <b>Associated Components</b> | 1                   |
| <b>Classification:</b>                   | Goods                                                                                                                                                                               | <b>Bid Supplements</b>       | 0                   |
| <b>Category:</b>                         | Electrical Supplies                                                                                                                                                                 |                              |                     |
| <b>Approved Budget for the Contract:</b> | PHP 528,865.68                                                                                                                                                                      | <b>Document Request List</b> | 0                   |
| <b>Delivery Period:</b>                  | 15 Day/s                                                                                                                                                                            |                              |                     |
| <b>Client Agency:</b>                    |                                                                                                                                                                                     | <b>Date Published</b>        | 06/06/2025          |
| <b>Contact Person:</b>                   | Nestor, Jr. A. Malunes<br>Municipal Assessor<br>4th Congressional District,<br>Anilao<br>Iloilo<br>Philippines 5009<br>63-33-3620459<br>63-33-3620459<br>engineeranolao01@gmail.com | <b>Last Updated / Time</b>   | 05/06/2025 14:58 PM |
|                                          |                                                                                                                                                                                     | <b>Closing Date / Time</b>   | 11/06/2025 10:00 AM |

#### Description

- 1.) 4 - pcs - Anchor, Expanding, 10,000 Pounds, 8 Way, Galvanized Steel
- 2.) 4 - pcs - Bolt, Thimble Eye, 5/8", X
- 3.) 18 - pcs - Bolt, Double Arming, 5/8" X18"
- 4.) 3 - pcs - Bolt, Double Upset, 5/8", X 10"
- 5.) 8 - pcs - Bolt, Oval Eye, 5/8" X 10"
- 6.) 4 - pcs - Bolt, Oval Eye, 5/8" X 12"
- 7.) 32 - pcs - Bolt, Machine, 1/2" X 6"
- 8.) 10 - pcs - Bolt, Machine, 1/2" X 10"
- 9.) 6 - pcs - Bolt, Machine, 5/8" X 10"
- 10.) 4 - pcs - Bolt, Machine, 5/8" X 14"
- 11.) 3 - pcs - Bolt, Single Upset, 5/8" x 10"
- 12.) 16 - pcs - Brace, Angle. 1-1/2" x 1-1/2" x 3/16", 60" Span
- 13.) 9 - pcs - Clamp, Hot Line, #2 - #2/0 ACSR Main to #2-#2/0
- 14.) 4 - pcs - Clamp, Anchor Rod Bonding, Single Eye
- 15.) 24 - pcs - Clamp, Loop Dead-end, #2/0 ACSR
- 16.) 15 - pcs - Clamp, Dead-end Strain, #2/0 ACSR
- 17.) 8 - pcs - Clamp, Guy Straight, 3 Bolt, Heavy Duty Steel
- 18.) 12 - pcs - Clevis, Secondary Swinging without Spool
- 19.) 2 - pcs - Shackle, Anchor, Forged Steel, Galvanized
- 20.) 977 - pcs - Conductor, Bare, ACSR #2/0, AWG 6/1
- 21.) 8 - pcs - Connector, Compression, YHO 200, #1/0-#2/0 ACSR Run to #6-#2
- 22.) 10 - pcs - Connector, Compression, YHO 300, #1/0-#2/0 ACSR Run to #1/0-#2/0
- 23.) 6 - pcs - Connector, Ground Rod (Clamp) for 5/8" Steel Rod
- 24.) 6 - pcs - Cutout and Arrester Combination, Porcelain
- 25.) 9 - pcs - Insulator, Pin Type, Porcelain, ANSI, Class 55-5
- 26.) 10 - pcs - Insulator, Spool, 1-3/4", ANSI Class 53-2

- 27.) 8 - pcs - Insulator, Spool, 3", ANSI Class 53-4
- 28.) 6 - pcs - HDPE Cross-arm Pin, 1" Long Shank, 14"
- 29.) 45 - pcs - Insulator, Suspension, 6", Porcelain, Clevis Type
- 30.) 15 - pcs - Nut, Eye, 5/8", Conventional
- 31.) 3 - pcs - HDPE Pole Top Pin 1" & 1-3/8"
- 32.) 4 - pcs - Rod, Anchor, Threaded, Single Eye, 5/8 x 7
- 33.) 15 - pcs - Rod, Armor, Preformed, #2/0 ACSR, Single Support
- 34.) 6 - pcs - Rod, Ground Steel, Galvanized, 5/8" x 10"
- 35.) 98 - pcs - Washer, Square, Flat, 2-1/4" x 3/16", 13/16" Diameter Hole
- 36.) 240 - pcs - Wire, Grounding, Aluminum Alloy, 3 Strand, #4 AWG
- 37.) 200 - pcs - Wire, Guy, Steel, Galvanized, 5/8" x 10"
- 38.) 4 - pcs - Pole, Steel 40', 3.0mm (50%)
- 39.) 1 - pcs - Pole, Steel 40', 3.0mm
- 40.) 16 - pcs - Cross-arm, Steel 3" x 4" x 8", 3.0mm
- 41.) 2 - pcs - A5
- 42.) 3 - pcs - C1
- 43.) 4 - pcs - C7
- 44.) 6 - pcs - M2-11A
- 45.) 4 - pcs - E1-2
- 46.) 4 - pcs - F1-3
- 47.) 3 - pcs - J5
- 48.) 4 - pcs - J6
- 49.) 2 - pcs - J15
- 50.) 4 - pcs - Pole Erection (40 Feet)
- 51.) 1 - pcs - Pulled Out of 30 Feet
- 52.) 3 - pcs - Pulled Out of 35 Feet
- 53.) 0.977 - pcs - Conductor Pay-out #2/0, AWG, ACSR
- 54.) 11 - pcs - M5-1
- 55.) 8 - pcs - M5-10
- 56.) 5 - pcs - M5-12
- 57.) 5 - pcs - M5-14
- 58.) 1 - pcs - M5-20
- 59.) 1 - pcs - M5-23
- 60.) 25 - lot - Retirement and Installation of 25KVA Transformer
- 61.) 11 - lot - Rehab of KWHR Meter
- 62.) 1 - lot - Engineering Expenses (Three Phase Line)
- 63.) 1 - lot - Hauling of Materials

**Line Items**

| Item No. | Product/Service Name                               | Description                                                                                             | Quantity UOM |     | Budget (PHP) |
|----------|----------------------------------------------------|---------------------------------------------------------------------------------------------------------|--------------|-----|--------------|
| 1        | CONVERSION OF SINGLE PHASELINE TO THREE PHASE LINE | IMPROVEMENT OF OPCEN (TRANSFORMER FOR OPCEN & APCF) CONVERSION OF SINGLE PHASE LINE TO THREE PHASE LINE | 1            | Lot | 528,865.68   |

**Other Information**

Submission of Quotation until June 11, 2025 @ 10:00 A.M.

**Created by** Nestor, Jr. A. Malunes

**Date Created** 05/06/2025

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.